BQ FOR SUPPLY & INSTALLATION OF WIND PUMP

No	**Description**	**Unit**	**Qty**	**Price/unit**	**Total**
	Main frame				
1	Rotor blade system	unit	1		
2	Transmission: Direct Drive, Variable Stroke (300-150mm)	unit	1		
3	Tower: Free Standing, 9m (30ft) Tall	Unit	1		
	Accessories				
4	A 70mm Deep Well Pump Cylinder (All Brass)	Pcs	1		
5	3" Gl. Pipes Class B of 3m each (Pump depth 72m)	Pcs	24		
6	Pump Rods (Pump depth 72m)	Pcs	16		
7	2" GI Pipe fittings, Air Bottle + Shroud	set	1		
8	2’’ GI Pipeline extension 6m anchored	m	2		
8	Stuffing Box complete	Pcs	1		
	Other costs				
9	Mobilization	Kms	1125		
10	Wind mill foundation/base	Lump sum	1		
11	Labour for installation	Lump sum	1		
	Grand Total				